



Specifications:

- All timber to be rough sawn White Oak with 1/4" chamfer throughout.
 - Timber Joints to be secured with White Oak or Locust Pegs.
 - Legs are 4x4, Top is 5x6, Girt is 2x6.
- Top has band sawn curve with 5/4 Pine rooflet and forest green metal flashing for added protection.
- Sign area has 3/8" cork over 1/2" AC Plywood mounted to 2x2 framing. Plywood is stained Mission Brown on back side.
- Door is of 1x2 kiln dried white oak with plexiglas® installed in dadoed groove. Door is hinged on top and has pin with hole to receive padlock (padlock not provided).
 - Back can serve as optional additional signage area..
- Posts to be buried minimum 4' below grade, backfilled with 3/4" crushed stone.

Single Unit: \$1000

2-4 Units: \$900

5 or more Units: \$850

Prices are F.O.B. Vershire, Vermont, Delivery quotes upon request.
Site preparation and installation are NOT included in unit cost.
Unit comes fully assembled, ready to install.

TimberHomes Vermont, PO Box 106, Vershire, VT 05079
(802) 685-7974 or (802) 685-3807 (fax)
info@timberhomesllc.com

Timo Bradley, David Hooke, Josh Jackson & Shannon McIntyre, owners