

Specifications:

• Foundation to be a granite boulder of approximately 500 lbs split approximately in half.

• Sills of 6x8 White Oak scribed to a boulder and secured with countersunk 5/8 x 10" Titan® Anchor (black) or equivalent per sill hidden under bench. Holes to be sealed against water with Tescon Vana® tape or equivalent.

• Uprights of Black Cherry 2x8 with through mortise and draw-bored 1" W. Oak Peg.

• Bench of 2x6 Slats and 3x5 Rib of Eastern White Cedar, assembled with 2 @ 14" Log Hog® (shown in green) or equivalent at 1/3 points, and secured to sills with 2 @ countersunk 4" Stainless Steel Screws (shown in red) per Slat and one at Rib.

Back of 2x6 Eastern White Cedar, assembled with 2 @ 8" Log Hog® (shown in blue) or equivalent, and secured to Uprights with 2 @ 4" Stainless Screw per Slat.

• 2" x 2" Through Tenon on Upright to Armrest joint.

• All timber to receive 1/4" chamfer throughout. Cedar slats and ribs are rough sawn. Sills are to be planed. Uprights are to be planed and coated with Heritage Natural Exterior Finish® or equivalent.

• Sites to be prepared by others with a 3" thick level pad of 3/4" crushed stone.

Options:

Upgrade sills and uprights to black locust and slats to white oak for better rot resistance - \$400

Single Unit: \$2,200 2-4 Units: \$2,150 5 or more Units: \$2,100

For photos and more information, visit our website: www.timberhomesllc.com/kiosks

Prices are F.O.B. Vershire, Vermont, Delivery quotes upon request. Site preparation and installation are NOT included in unit cost.

TimberHomes Vermont, PO Box 106, Vershire, VT 05079 Contact: Mikey@timberhomesllc.com, (802) 685-7974 ext. 3 Timo Bradley, David Hooke, Josh Jackson, Shannon McIntyre, Andrew Catlin, & Helen Doyle, owners

