



Specifications:

- Posts are Black Locust, all other timbers are White Pine.
 - Principle timber joints secured with White Oak pegs.
- Posts are 5.5"x5.5"; Girts are 4"x5"; Ties are 5.5"x5"; Plates are beveled 3"x4"; Ridge is 3"x3".
 - Roof is rough sawn pine boards with channel drain roofing.
 - Signboard 42"x32" of 3/4" tongue-in-groove eastern white cedar.

Installation:

- Kiosk comes in three parts: roof assembly, signboard assembly, and posts
- Purchase will include installation directions including exact center-to-center measurements for excavation
 - After digging holes, installation should take crew of 4 strong people about 1 hour
 - We strongly recommend burying 12" x 4' sonotubes in post locations
 - Insert posts into tubes and backfill with clean crushed stone.
 - Concrete footings are not necessary, and burying bottoms of posts in concrete is not recommended

Recommendation:

The Black Locust posts are the best all natural wood choice available from the Northeastern forest. They should have a service life of many decades with an in ground installation. Regardless, we strongly recommend:

- Following THVT's best installation practices described on the website and in the installation directions
- Annual inspection of the post bases to ensure safe post condition, especially after the first decade of service.

Options:

THVT's Classic Kiosks have a range of possible roof and signboard customizations as well as possible add-ons. Please consult our website.

If needed, THVT can supply steel post bottom brackets. Please inquire for details.

For photos and more information, visit our website: www.timberhomesllc.com/kiosks

Prices are for pickup in Montpelier or Vershire, Vermont. Delivery quotes upon request.
Site preparation and installation are NOT included in unit cost.

TimberHomes Vermont | 21 Fork Road | Montpelier, VT 05602
Contact: info@timberhomesllc.com, (802) 685-7974
Made in Vermont by a Worker-Owned Company